



# ShurePlus MOTIV

ShurePlus MOTIV™ Recording App for Android

The Shure Android audio recording app, ShurePlus MOTIV, user guide.  
Version: 4.0 (2021-J)

# Table of Contents

|   |           |   |           |
|---|-----------|---|-----------|
| <b>ShurePlus MOTIV ShurePlus MOTIV™ Recording App for Android</b> | <b>4</b>  | Compressed Format Recording                     | 17        |
| <b>General Description</b>  | <b>4</b>  | Bit Depth and Sample Rate                       | 18        |
| Features  | 4         | <b>Recording Tips</b>                           | <b>18</b> |
| <b>Quick Setup</b>  | <b>4</b>  | Turn Off Notifications                          | 18        |
| <b>The MV88+ Microphone</b>                                       | <b>4</b>  | Use the Dark Theme                              | 18        |
| Microphone Orientation  | 5         | Keep Screen Awake During Recording              | 18        |
| MV88+ Outputs   | 6         | Select Your Orientation                         | 19        |
| <b>Aiming the Microphone</b>                                      | <b>6</b>  | Use Lock Mode to Lock In Your Sound             | 19        |
| Audio Recording   | 7         | Record in Mono                                  | 19        |
| Audio Interview (Tabletop)  | 7         | Record in Stereo                                | 19        |
| Landscape (Horizontal) Video Recording                            | 8         | Monitor your Recordings                         | 19        |
| Portrait/Selfie (Vertical) Video Recording                        | 8         | Capture the Complete Performance                | 19        |
| Video Interview   | 8         | Keep equipment connected during updates         | 19        |
| Handheld Recording  | 9         | Backup Reminders                                | 19        |
| <b>The MOTIV App</b>  | <b>10</b> | <b>Using MV88+ with your Mac and PC</b>         | <b>19</b> |
| Device Setup  | 10        | <b>Library</b>                                  | <b>20</b> |
| Preset Modes  | 12        | Playback  | 20        |
| Custom Presets  | 12        | Converting Multiple Files                       | 21        |
| Polar Pattern Selection (Stereo and Mono Settings)                | 13        | Using the Files App to Manage the MOTIV Library | 22        |
| Direct Monitoring Blend   | 14        | Recovering Recently Deleted Files               | 22        |
| <b>Advanced Mic Settings</b>                                      | <b>15</b> | <b>Editing Your Audio</b>                       | <b>22</b> |
| Limiter   | 15        | Navigating The Timeline                         | 23        |
| Compressor  | 15        | Creating A Loop                                 | 23        |
| High Pass Filter  | 15        | Markers   | 24        |
| Left-Right Channel Swap   | 15        | Editor  | 24        |
| Equalizer   | 15        | Editing in Split Mode                           | 25        |
| Demo Mode   | 16        | <b>Enhance</b>                                  | <b>26</b> |
| <b>Record</b>   | <b>16</b> | Using Enhance to Improve your Recordings        | 26        |
|   |           | How Does Enhance Work?                          | 26        |
|   |           | <b>Sharing MOTIV Recordings</b>                 | <b>26</b> |

---

|                         |    |   |           |
|-------------------------|----|---|-----------|
| Save to Camera Roll     | 26 | <b>Troubleshooting</b>                                | <b>28</b> |
| Customize Track Artwork | 27 |   |           |
| Save to Dropbox™        | 27 | <b>System Requirements and Compatibility: Android</b> | <b>29</b> |
| AirDrop® with MOTIV     | 27 | System Requirements and Compatibility: Windows        | 29        |
| Save to iTunes          | 27 | <b>Certifications</b>                                 | <b>29</b> |

---

# ShurePlus MOTIV

## ShurePlus MOTIV™ Recording App for Android

---

### General Description

The ShurePlus MOTIV app provides instant recording for your Android device. Adjust your microphone settings and record uncompressed audio. Then share your files via text, email, Google Drive™, and more.

### Features

- Plug-and-Play operation
- Flexible recording control includes gain settings
- Dark and light display options
- Support for mono and stereo USB audio devices
- Bluetooth® playback support
- Multiple bit depth and sample rate options
- Preset mode options when used with MOTIV microphones
- Automatic file save in case your microphone becomes disconnected.

---

### Quick Setup

1. **Plug the microphone into the USB Input on the Android device.**

The LED on the MOTIV device illuminates when the connection is made.

2. **Download and open the app.**

Android requests permission to use the external device each time. Check "Use by default for this USB Device".

3. **Turn on Airplane Mode and Do Not Disturb before recording.**

This will prevent phone calls or notifications from interrupting your recording.

4. **Check audio levels and adjust microphone settings.**

Select a preset mode or manually adjust microphone gain. See the "Advanced Mic Settings" topic for information on advanced features.


5. **Start recording.**

*Tip: Gain adjustments can be made while recording, but to avoid audible artifacts, test settings prior to pressing record.*

---

### The MV88+ Microphone


The MV88+ features two capsules: one capsule has a cardioid pattern and picks up sound directly in front of the microphone. The other is bidirectional and captures sound from the left and right sides.




## Microphone Orientation

Rotate the microphone barrel in the mic clip to ensure that your stereo recordings are accurate. Point the front of the microphone toward the sound source. For landscape (horizontal) recording, position the L and R indicators to the right and left. For portrait (vertical) recording, simply rotate the microphone barrel in the mic clip.

**Note:** The app has a Left-Right Channel Swap to flip the audio channels.



## MV88+ Outputs



- 3.5mm monitor output for connecting to headphones and earphones
- Send audio to your recording device using the micro-B USB port

## MV88+ LEDs

| iOS                               | Android/Mac/PC     |
|-----------------------------------|--------------------|
| Green: Mic active, audio flowing  | Green: Power is on |
| Amber: Error                      |                    |
| Flash Amber: Firmware is updating |                    |
| Red: Microphone is muted          |                    |
| Flash Red: Audio is clipping      |                    |




# Aiming the Microphone

The following suggestions are for typical use cases. Keep in mind that there are many effective ways to record a source. Experiment to find what works best for you. The MV88+ fits into a standard A25D mic clip. So, you can place it anywhere that you can put a mic stand.

**Tip:** For correct stereo orientation, ensure that the Shure name is clearly visible on the top of the microphone. If the name is not visible, adjust the microphone accordingly.


## Audio Recording

Position your recording device so you can monitor the recording. Aim the front of the microphone toward the source, with left and right sides of the microphone barrel facing the appropriate directions.




## Audio Interview (Tabletop)

Attach the mic clip directly onto the Manfrotto mic stand. Select the MONO BIDIRECTIONAL polar pattern in the MOTIV app. Point one side of the microphone barrel toward the subject and the other toward the interviewer.



## Landscape (Horizontal) Video Recording

Aim the front of the microphone toward the source. Ensure that the left and right sides of the microphone barrel are facing the appropriate sides.



## Portrait/Selfie (Vertical) Video Recording


Aim the microphone toward yourself and select Left - Right Swap.

**Tip:** If you begin shooting in portrait mode, video will remain in portrait mode even if device orientation is turned to landscape.

## Video Interview

- To record audio from on-camera audio only, select the CARDIOID polar pattern and point the microphone toward your subject.






- To capture the voices of both the on-camera subject and the off-camera interviewer, select the MONO BIDIRECTIONAL polar pattern in the app. Position the microphone with the left and right sides facing each person.

## Handheld Recording

The legs collapse to create a portable hand-held stand.



---

## The MOTIV App


Use the MOTIV app to change microphone settings and to record, edit, and share audio. The device stores the most recently used settings for quick setup each time you record.

**Tip:** Turn on Airplane Mode and Do Not Disturb to prevent interruptions to the recording caused by phone calls, text messages, or alerts.

## Device Setup



*Tap Device on the navigation bar to access microphone settings*








**① Notifications** The top row displays which device is connected. A red flashing dot next to the name let you know whether recording is active. The charms show which advanced features are on. Tap the headphone icon to access direct monitoring control. Tap the lock to lock or unlock the settings.

**Note:** Lock the settings to prevent accidental changes to settings when handling your device during recording. When mic settings are Locked, the setting screen is grayed out.

- ② **Input Meter** Displays the strength of the input signal and whether that signal is mono or stereo. The loudest peaks should reach within the target range (indicated by the shaded region between -12 and -3 dB).
- ③ **Microphone Gain** Adjust the mic gain slider to set the volume of the sound source.
- ④ **Custom Presets** Tap the caret to quickly access your saved presets. Or tap the Save button to save current settings. See Custom Presets for more information.
- ⑤ **Preset Modes** Set stereo width, equalization, and compression for specific applications. See "Preset Modes" for more information.
- ⑥ **Polar Pattern Selection** Swipe to choose your pick-up pattern. Use the handles to adjust the width of the stereo image.
- Tip:** Consider the location of the microphone and the size of the sound source when adjusting the width. For example, a large orchestra or ensemble recording benefits from a wide stereo image, which increases separation between instruments. Speech benefits from a narrow width, which improves clarity and rejects ambient (room) sound.
- ⑦ **Stereo Width Handles** Use the dots to quickly set stereo width.
- ⑧ **Advanced Features** Fine tune your audio recording with limiter and compressor controls, high pass filter, left-right swap, and equalization settings.

## Preset Modes

Five selectable modes optimize settings for gain, stereo width, equalization, and compression. Set the microphone level and try the modes to find which sounds best. Preset modes can affect the strength of the input signal, so adjust the microphone level as needed after changing presets.

| Mode   | Application                          | Characteristics  |
|--|--------------------------------------|--|
| <br><b>Speech</b>    | speech                               | Narrow stereo width to reject background noise, equalization that emphasizes clarity and fullness, and gentle compression.   |
| <br><b>Singing</b>  | solo or group vocal performances     | Medium stereo width with subtle equalization to add richness and clarity for a natural sound.  |
| <br><b>Flat</b>     | any                                  | An unprocessed signal (no equalization or compression settings used). Adds flexibility when processing the audio after recording.  |
| <br><b>Acoustic</b> | acoustic instruments and quiet music | Medium stereo width with transparent compression to smooth out volume spikes and bring out quiet passages. The equalizer setting emphasizes detail and an overall natural sound. |
| <br><b>Loud</b>     | live performance and louder sources  | Wide stereo to increase separation between sources. Equalization further improves definition by reducing frequencies that can make the instrumentation sound crowded.            |

## Custom Presets

Create and save custom presets to quickly access frequently used mic settings.

1. Start with the preset mode that best suits your application needs.
2. Adjust advanced settings, like compression, for clarity and consistency.
3. Tap Save to rename your preset, or use the default name.
4. Custom preset is added to your list.



To access saved presets:

1. Tap the caret (arrow) in the Preset row to view your list of saved presets.
2. Tap custom preset and Apply Preset to instantly apply gain, stereo, equalization, and compression preferences.

**Tip:** You can save a custom preset at any point by tapping Save.

## Polar Pattern Selection (Stereo and Mono Settings)

The following demonstrates microphone capsule pick-up patterns. When operating in a mono mode, stereo width is not adjustable.

|   |                    |   |
|---|--------------------|---|
|    | Stereo             | Front = On<br>Sides = On  |
|    | Mono Cardioid      | Front = On<br>Sides = Off   |
|    | Mono Bidirectional | Front = Off<br>Sides = On   |
|  | Raw Mid-Side       | Front = On<br>Sides = On<br><br>See "Raw Mid-Side Output" for more information. |

### Raw Mid-Side Output

For increased post-processing flexibility, use the Raw Mid-Side setting. This records signal a 2-channel signal with a stereo image that can be adjusted even after the tracks have been recorded:

**Left:** Cardioid (front)

**Right:** Bidirectional (sides)

Use the Raw Mid-Side setting with audio recording applications that have a mid-side stereo matrix decoder. Or use the manual decoding instructions to adjust the stereo image of the recorded tracks.


### Manual Decoding and Stereo Width Adjustment

If your digital audio workstation software (DAW) has no mid-side decoder, use these steps to adjust and manipulate the stereo image:

1. Extract the left and right audio signals from the 2-channel Raw Mid-Side file as individual mono tracks.
2. Create 3 blank audio tracks:
  - **First track:** Use the audio signal (front/cardioid) from the **left channel only** as a mono track, panned to the center.
  - **Second track:** Use the audio signal (side/bidirectional) from the **right channel only** as a mono track, panned all the way to the left.
  - **Third track:** Copy the side/bidirectional signal from the second track. Pan this track all the way to the right and **reverse the phase**.

- Group the right and left side tracks, and set the volume at the same level for simultaneous adjustment. Increasing the volume of the grouped tracks increases the stereo width, while decreasing their volume narrows the width.


**Advanced tip:** Using compression with a fast attack setting on the grouped tracks keeps transients (the first part of a sound, such as when a drum stick strikes a cymbal) toward the center of the stereo image and allows them to expand within the stereo field as the sound decays.



**Manual Decoding of Raw Mid-Side Audio**


## Direct Monitoring Blend

There are two ways to access the Direct Monitoring slider when you want to adjust your monitor source. Tap the input meter to view the mic gain and monitoring blend sliders. Or you can view the slider by tapping the headphone icon in the device settings tab.



Use the direct monitoring slider to determine how much of each input you hear. For best results, start monitoring at the mid-point and adjust.

- Move the slider towards Mic to hear more of the audio that is being currently recorded by the microphone.
- Move the slider towards Playback when you want to listen to the previously recorded audio and less of the audio coming in to the microphone. This is useful for when you want to review your recording.



*As one source increases, the other source decreases.*

# Advanced Mic Settings

After you have selected the preset mode for your application, fine tune the sound of your recording with limiter, compressor, and equalizer controls. Your settings will be retained in the microphone when using other audio and video recording applications.

## Limiter

Toggle the limiter on to set an input threshold and prevent distortion from volume peaks in your recordings.

## Compressor

Choose no compression, or select light or heavy compression to control volume when your sound source is dynamic. The compressor will narrow the dynamic range, which means that quiet signals are boosted and loud signals are lowered.

## High Pass Filter

Choose no HPF for the most natural sound. Or select 75 Hz or 150 Hz to reduce wind noise, room noise, or proximity effect.

**75 Hz Low frequency cutoff** Provides a 6 dB-per-octave cutoff at 75 Hz. Helps eliminate floor rumble and low-frequency room noise from heating and air conditioning systems. This setting may also be used to compensate for proximity effect or to reduce low frequencies that make an instrument sound dull or muddy.

**150 Hz Low frequency rolloff** Provides a 6 dB-per-octave rolloff filter at 150 Hz. Use this to compensate for proximity effect or to reduce low frequencies that could make an instrument sound dull or muddy.

## Left-Right Channel Swap



For stereo recordings, use Left - Right Swap to flip the left and right audio channels to match the stereo image to the video. For example, when using video to record yourself.


**Tip:** Use the L and R indicators on the microphone barrel. This way you can set Left - Right Swap before you start to record.

## Equalizer



Change the preset modes to hear the DSP changes, and then use the equalizer to boost or cut bands of frequencies to improve sound clarity.


**Note:** Equalization within presets will not be displayed. However, the equalizer graphic in the advanced settings status bar displays the user-selected equalization.



*Tap to access the MOTIV equalizer. Equalization changes are displayed in the equalizer image.*

EQ persists between preset mode changes.

## Demo Mode



Demo mode allows you to test out all devices in the MOTIV series.

1. Swipe through the list to see the available devices.
2. Tap Learn More for more information about each device. Or tap Next to explore the microphone settings.


**Note:** Settings in demo mode are for demonstration and are not saved within the app. Demo mode is only available when there is no microphone plugged in to the device.

## Record



*Tap Record on the navigation bar to access the record button and timeline.*





Record Settings

① **Connected Device Status** Status displays the connected MOTIV device. Red flashing dot indicates that recording is in progress.

② **Settings Status** Displays the icons for advanced settings that are currently enabled.

③ **Microphone Gain** Adjust the volume of the sound source. Keep levels in the target range (indicated by the shaded region on the input meter).

④ **Timeline Display** Displays the waveform of the sound while recording.

- **Stereo Recording:** A complete waveform is shown.
- **Mono Recording:** Half of the waveform is shown.

⑤ **Record Time Remaining**

⑥ **Bit Depth and Sample Rate** Use the drop-down menu to select your bit depth and sample rate. See "Bit Depth and Sample Rate" for more information.

⑦ **Track Information** Displays the name, file format, and size of the recording in progress.

⑧ **Record Control Bar** The Marker button, Record/Pause button, and the Done check mark button.

**Note:** The maximum file size for a recording is 2GB, approximately 2 hours of record time. This limitation maximizes app performance. Continuous recording for more than 2 hours will generate a second file.

## Compressed Format Recording

The MOTIV app records uncompressed audio files to provide the highest quality recording. However, you might find it more useful to record in a compressed file format. Compressed files take up less storage space allowing you more space on your device to record. It's also easier to share compressed files by message or email because compressed files use less data. Con-

sider using a compressed format for recording demos or initial ideas because in this case it is more important to capture the idea than have the highest possible fidelity recording.

If you are unsure about which format to choose, start with the highest quality setting. You can always compress files later from your library if you find that you require smaller files sizes. See the Supported Audio Formats section to learn about the file formats that are available to you.

**Remember:** You can convert compressed audio to an uncompressed format, uncompressed audio to a compressed format and one type of compressed format to another. However, only WAV files can be edited. If you need to edit a file, convert the file to a WAV file first.

## Bit Depth and Sample Rate

Find the Bit Depth and Sample Rate settings in the drop-down menu on the right side of the record window. Select a lower sample rate when it is useful to have a smaller file, for example, when recording speech or a podcast for download. Select a higher sample rate for music and dynamic recordings.

If no alternate is selected, MOTIV will record audio at 24/48 kHz. However, the following bit depths and sample rates are supported.

| Bit Depth | Sampling Rate |
|-----------|---------------|
| 24        | 48 kHz        |
| 24        | 44.1 kHz      |
| 16        | 48 kHz        |
| 16        | 44.1 kHz      |

## Recording Tips

### Turn Off Notifications

When you plug a MOTIV device into your Android device, a message prompts you to enable Airplane Mode and Do Not Disturb mode. Enable these modes to avoid interference from phone calls, messages, and notifications which add static to recordings. Android devices can't make calls and record USB audio at the same time. When you receive a phone call, recording stops.

### Use the Dark Theme

Select the Dark screen option to change the app display from light gray to very dark gray. The darker display is ideal for discreet recording in low-light situations. A darker screen also conserves battery life.

You can access the theme appearance setting by going to Menu > Settings > Appearance

### Keep Screen Awake During Recording

Select the Keep Awake While Recording option so you can continuously monitor gain levels during longer recording sessions without the screen going dark.

You can access the Keep Screen Awake option by going to Menu > Settings > Keep Screen Awake During Recording.

**Note:** Disabling sleep mode will affect battery time while recording.

## Select Your Orientation

If you are using the Shure MOTIV app to record video, set your screen orientation to either landscape or portrait before pressing record.

## Use Lock Mode to Lock In Your Sound

When you've tested your audio and have found the levels that you like, turn on Lock mode to prevent accidental adjustment, and ensure that your audio quality remains consistent.

## Record in Mono

Record in mono to increase your available record time or when recording a single source, like vocals, that would benefit from less ambient noise. Select the Mono Cardioid or Mono Bidirectional polar pattern and audio from all capsules are summed to a single channel. The input meter will indicate mono recording by displaying the top half of the waveform. MOTIV supports third-party microphones with mono recording.

## Record in Stereo

Rotate the MV88+ barrel in the mic clip to accommodate portrait or landscape recording. L and R are labeled to show stereo orientation of the microphone. The stereo image is accurate if the Shure logo is facing upward.

## Monitor your Recordings

To make sure that your recordings sound great, plug headphones directly into the headphone output on your MOTIV device.

## Capture the Complete Performance

To ensure that you capture the entire sound source, start your recording before the performance starts and edit the recording later to trim any silence.

**Note:** If your microphone accidentally becomes disconnected during recording, MOTIV will automatically stop the recording. The save file dialog will appear, prompting you to name and save your audio.

## Keep equipment connected during updates

Keep the MOTIV device connected to your mobile device when updating to ensure that there are no update issues.

## Backup Reminders

You will be prompted to back up your recordings. We recommend that you periodically back up your MOTIV files to another computer or device. This allows you the freedom to edit or delete files in the app and remain confident that you'll always have a backup stored somewhere else. Additionally, you will regain space on your device so you can confidently record long recording sessions without worrying about not having enough space.

You can schedule the frequency of backup reminders by going to Menu > Settings > Backup Reminders.


---

## Using MV88+ with your Mac and PC

MOTIV microphones do not require special drivers and are compatible with most Mac or PCs. The MV88+ settings (except for mic gain) cannot be adjusted via computer, however, the microphone does retain its last settings as configured by the MOTIV app.

**Note:** USB-A cable is not included.

# Library



## ① Library Search/Sort/Select

- **Search:** Search for files in your library by file name or file type.
- **Sort:** Tap the sort icon to organize files by name, date, size or file type.
- **Select:** Use the Select button to choose one or multiple recordings to convert, share, or delete.

② **Sort Order** Tap the caret to display the tracks in order or reverse order.

③ **Track List** Displays your list of recorded tracks.

④ **Recently Deleted** Your recently deleted files will be stored here for 30 days. See the Recently Deleted files topic to learn how to recover files.


## ⑤ Audio Player Bar

- Tap the track name to open the playback window
- Tap the Edit scissors icon to access the file Editor.
- Play and pause recordings.
- Tap the three dots to rename, share, convert file format, add artwork, or delete files.

**Note:** iOS users have the ability to search for files in the MOTIV Library by using the Spotlight feature.

# Playback

Double-tap the track name in the audio player to access the Playback window.




① **Track Information** Displays the name of the currently playing track, including file format, bit depth, sample rate, and stereo or mono.

② **Track Artwork** Keep the MOTIV artwork. Or customize your artwork with images from the photos in your device. See "Customize Track Artwork".

③ **File Information** Displays the record date and time, and the microphone that was used.

④ **Playback Timeline** See where you are in the track as it progresses. The time elapsed and time remaining are displayed below the timeline.

⑤ **Playback Controls** Edit, Rewind, Play/Pause, Fast-Forward, and Loop your track.



*Playback in horizontal view*

## Converting Multiple Files

Shure MOTIV allows you to convert, share, or delete multiple files at a time. Only WAV files can be converted.

1. Tap Select in the top-right corner of My Recordings.

2. Select all the files that you want to convert. A blue check mark will appear next to selected files.
3. Tap Save As to display conversion options. Converting the files adds the new files to the My Recordings list.


## Using the Files App to Manage the MOTIV Library

Access your MOTIV audio files from inside the Files app. The MOTIV app will create a MOTIV folder inside Files, including a recently deleted folder inside the MOTIV folder. Here you can copy your files to other folders or share to other apps on your device if those apps support file sharing. When you copy or move your files outside the MOTIV storage, you can ensure that those files will not be deleted if the MOTIV app gets uninstalled.

**Note:** Any changes made to MOTIV recordings in the Files app will be reflected in the MOTIV app. This means that if you change a file name or delete a track in Files, you will see those changes or deletions in the MOTIV app library. MOTIV and the MOTIV folder in Files remain consistent. If you move a track in Files to another location, that track will no longer show up in the MOTIV library. Also, if you were to add a file to the MOTIV folder in Files, that would show up in the MOTIV app library.

## Recovering Recently Deleted Files

Files that you no longer need can be deleted and will disappear from your library. However, you might find that you have mistakenly deleted a file that you want to keep. In this case, the Recently Deleted folder is a temporary safety net that will store files for 30 days before permanently deleting them.



# Editing Your Audio



*Tap Edit to access editing controls for each track.*

The MOTIV Editor allows you to polish your recordings before sharing them with friends or online.

There are two edit mode options:

- Split Mode allows you to split a long audio file into one or more separate tracks. This is useful when you've recorded a long performance and want to be able to listen to different sections individually.
- Trim Mode lets you trim the start and end of your recorded track.


## Navigating The Timeline

There are three ways to move around the timeline.

- Double tap the timeline to bring playhead to current view.
- Use the markers to move the playhead to a specific point.
- Tap and drag the red playhead bar to a new point in the timeline.

Press Play to begin playback from that selected point.

Pinch two fingers together to zoom out. Pinch apart to zoom in.



*Use Landscape mode in the Editor to view more of the waveform.*

## Creating A Loop



Create a loop to isolate and repeat a selection of audio.

- Select the Loop button to select the entire track. The waveform in the highlighted blue area will be looped.
- Select and drag the markers on the timeline to adjust your loop.
- Press Play to hear the loop and adjust until you find the best sound.

# Markers



Markers are audio bookmarks that allow you to return to specific points in your recording. They do not affect playback start and stop points but are useful for reference. When used in Split mode, the marker placement determines the split point for the file. Markers are identified by hour, minute, second, and millisecond (00:00:00:00), however they cannot be placed closer than one second apart from one another.

## Markers in Record Mode

**Adding a marker:** Tap the Marker button to insert a marker at the playhead location.

## Markers in Edit Mode

The marker list opens with Start and End markers for your audio track.

**Playback from a specific point:** Tap any marker to begin playback from that marker point.

**Adding a marker:** Press the plus sign to insert a marker at the playhead location.


**Moving a marker:** Press and drag an existing marker to a new location on the timeline.

**Using the marker list:** Tap the marker in the list to move the playhead to that location.

**Renaming markers:** Press and hold the marker label in the list.

**Deleting markers:** Swipe left on the marker in the list to reveal the delete option.

# Editor



① **Timeline Display** See your entire timeline. Zoom in for precise editing.



- ② **Trim / Split Select** Select your edit mode.
- ③ **Marker List** All recordings begin with Start and End markers. See "Markers" for more information.
- ④ **Add Markers** Click to add a marker at the playhead position.


## Editing in Trim Mode

Trim mode is used to trim the extra space from the Start and End of your audio track.

1. Go to My Recordings to select the audio file that you would like to edit.
2. Select the Edit icon to open the Editor.
3. The blue lines represent the Start and End points of your track. Select and drag the blue line to adjust Start and End times.
4. Select Loop to have the loop play in a circle and allow you to hear your track before committing to edits.

**Tip:** To undo the last action on your iOS device, just shake the device. You will receive a pop-up asking you to Undo the last action or Cancel.

## Editing in Split Mode



- ① **Timeline Display** See your entire timeline. Zoom in for precise editing.
- ② **Trim / Split Select** Select your edit mode.
- ③ **Playback Controls** Loop, Rewind, Play/Pause, or Add Bookmarks to your track.
- ④ **Marker List Item** Displays name and position in hours, minutes, seconds, and milliseconds.

Use Split Mode when you have a long audio file that you'd like to divide into smaller audio files. Create new edited files while keeping your original file intact.

1. Go to My Recordings to select the audio file that you would like to edit.
2. Select the Edit icon to open the Editor.
3. Place a marker at the point where you want to split the audio.
4. Select Split.
5. Keep the original file format or select a new one.

- MOTIV uses the file name but adds numbers to the names of your new, separated tracks. In Split mode, when you divide a track in half, My Recordings now displays three tracks. The original track remains intact and the first and second tracks that were created with the Split edit.

**Note:** Double tap on the timeline to zoom in to a location. The closest possible zoom length is two seconds. After you reach the closest zoom, the double-tap will zoom out.

## Enhance

Enhance is a quick way to make recordings sound better and more suitable for sharing. By selecting one of the three levels, low, medium, or high), you can automatically adjust the loudness, compression and other qualities of your recording.

|               |   |
|---------------|---|
| <b>Low</b>    | Best suited for speech recordings                 |
| <b>Medium</b> | Best suited for quiet musical content             |
| <b>High</b>   | Best suited for loud or amplified musical content |

## Using Enhance to Improve your Recordings

To preview the changes made by the enhance feature, select the part of your audio file where you would like the preview to start. Once your file is processed, enhance can adjust settings.

- Place the playhead (red bar) where you would like the preview to start.
- Tap Low, Medium and High to hear how your file changes with different enhance levels.
- Select the level that sounds best and then Save. You can save the file or rename it to create a new file.

**Note:** Every time the file is changed, you will need to apply Enhance again to process the changed file.

## How Does Enhance Work?

By selecting one of the three Enhance levels (low, medium, high), a series of processing algorithms are applied to your file. The amount of processing depends on the level that you have selected. Loudness, compression, soft and hard limiting are applied to all levels. Automatic equalization is applied to the medium and heavy Enhance levels. Preview the levels and select the one that sounds best. Save the file with a new name or preserve the original track and create a new enhanced file with a new name.

**Tip:** Start by applying enhance to a single track. It will be faster to process each file individually. Also, different tracks will have different levels and tones. By processing one file at a time, you can be sure that enhance is getting the best sound out of each track.

## Sharing MOTIV Recordings

### Save to Camera Roll

Convert your audio into a video file that can be easily shared to social media from your iOS device Camera Roll.

- In My Recordings, select the file you want to convert.
- Select the Share button.
- Select Save to Camera Roll.
- The conversion will happen automatically. Large files will take longer to convert.

**Note:** The first time you save to Camera Roll you will be asked to grant permission for file sharing between apps. If you accidentally dismiss permissions, you can always change access in the iOS device settings. Granting permission creates a MOTIV folder inside the Camera Roll.

- When the conversion process is complete, you will receive a notification letting you know that the save to Camera Roll was successful and your track is available for sharing.

## Customize Track Artwork

You have the option to add an image to your recording.

- In the My Recordings tab, select the file that needs artwork.
- Tap the three dots next to the file name.
- Select Add Artwork to view available image files.
- Select a photo. If you decide to change the artwork, repeat the process and select another image.

## Save to Dropbox™

Save your MOTIV files to Dropbox to store backup copies, free up space on your iOS device, or share to social media.

- Open the MOTIV app and go to My Recordings.
- Tap the Select button to choose one or multiple files.
- Select share and choose Dropbox.

**Note:** You may need to grant access between MOTIV and Dropbox. Selecting "Allow" creates a MOTIV folder inside Dropbox and links the apps.

- When the file successfully uploads, the file saved notification appears.

**Note:** Large files may take longer to upload.

Now that your file is uploaded to Dropbox, you can store backup copies of your recordings or share them on social media.

## AirDrop® with MOTIV

MOTIV supports the ability to AirDrop WAV files to selected contacts.

- Open the MOTIV app and go to My Recordings.
- Tap the Select button to choose one or multiple files.
- Select Share and then More to see your AirDrop contacts.


## Save to iTunes

Use iTunes to easily transfer audio files between your desktop computer and iOS device.


- Connect your iOS device to a computer and open iTunes.

**Note:** The most current version of iTunes is recommended.


- Select your device icon and then select "Apps" from the settings column.



3. Select MOTIV from the file sharing section at the bottom of the screen. You might need to scroll all the way to the bottom using the far right scroll bar. This will display your MOTIV documents.



4. Highlight the recordings you'd like to save and choose the "Save to" button.



**Note:** Large files may take longer to upload.

Now that your files are downloaded to your computer you can add them to the iTunes library or import them into any audio editing program.

**Note:** Use the add file button to upload audio from your computer to the MOTIV app.

## Troubleshooting

| Issue   | Solution   |
|---|--|
| <b>MOTIV device is plugged in, but the device does not illuminate and is not recognized by the app.</b> | Ensure that the cables are connected in correct order; MOTIV device to Micro-B USB cable to On-The-Go (OTG) cable to Android device.   |
| <b>Microphone is plugged in, but the volume meter does not register a signal.</b>                       | Unplug and re-seat the microphone when the name of the microphone is not visible in the status bar.  |
| <b>Microphone has been resealed, but the volume meter still does not register a signal.</b>             | If the lights on the MOTIV device are still off, your phone may not provide enough power. Check device settings to enable USB power. And ensure that the connecting cable is an On-The-Go (OTG) cable.                           |
| <b>Audio sounds bad or distant.</b>   | To ensure that you are receiving audio from the microphone and not a built-in mic, unplug and reseat the microphone. The top left corner of the screen will identify the Shure MOTIV microphone when the microphone is in place. |

| Issue              | Solution   |
|--------------------|--|
| Audio is distorted | Use the audio meter to ensure that volume peaks are within the target range. If the level reaches the red peak indicator of the input meter, turn the gain down. |

---

## System Requirements and Compatibility: Android

Will work with any Android device that has:

- Android Oreo 8.0 and higher
- USB Host Power Requirement of  $\geq 100$  mA
- USB Audio Class 1.1 support and higher

Android is a trademark of Google Inc.

**Note:** See <https://www.shure.com/MOTIVcompatibility> for information on supportive Android devices.

## System Requirements and Compatibility: Windows

- Windows 10
- 64 bit
- Minimum 2 GB of RAM
- Minimum 500 MB of hard disk space

---

## Certifications

### Android Compatibility

This equipment is compatible with Android devices that support USB Audio Class 2.0 and USB-C connectivity. Not all Android devices are compatible. Android is a trademark of Google Inc.

The ShurePlus MOTIV App for Android is not affiliated with or otherwise sponsored by Dropbox, Inc.